

SECTION 10240
EQUIPMENT SCREENS

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:

1. Pre-formed thermoplastic panel for enclosing roof top mechanical equipment.
2. Aluminum assembly framing for direct attachment of screening panels to mechanical equipment; no base or curb required unless shown otherwise on drawings..
3. Aluminum extrusions to permit easy access to mechanical equipment for servicing.

B. Products Not Installed or Furnished in This Section:

1. Touch-up painting required for scratches and screw heads.
2. Field painting of prime painted screens

1.03 REFERENCES

A. American Society for Testing and Materials: Standard Specifications for

1. ASTM B 221-96 - Aluminum and Aluminum Alloy Extruded Bars, Rods, Wire Profiles, and Tubes.

B. The Aluminum Association, Inc.

1. AA ADM-1516166 (1994) Aluminum Design Manual

C. American Society of Civil Engineers.

1. ASCE 795 Minimum Design Loads for Buildings and Other Structures.

1.04 SYSTEM DESCRIPTION

A. Design Criteria:

1. Manufacturer is responsible for the structural design of all materials, assembly and attachments to resist snow, wind, suction and uplift loading at any point without damage or permanent set.
2. Framing shall be designed in accordance with the Aluminum Design Manual to resist the following loading:
 - a. ASCE 795 Minimum Design Loads for Buildings and Other Structures; American Society of Civil Engineers.

1.05 SUBMITTALS

- A. Product Data:** Submit manufacturer's catalog data, detail sheets, specification and other data sufficient

to indicate compliance with these specifications.

B. Shop Drawings: Indicate layouts heights, component connection details, and details of interface with adjacent construction. Mark data to indicate:

1. Roof top mechanical equipment to be enclosed.

C. Samples:

1. Samples of Materials: Thermoplastic panels and colors.

2. Color Selection: Submit paint chips with full range of colors (minimum of eight) available for Architect's selection.

D. Certification: Manufacturer's Certificate of Compliance certifying that thermoplastic panels supplied meet or exceed requirements specified.

E. Closeout Submittals: Warranty documents, issued and executed by manufacturer, countersigned by Contractor.

1.06 QUALITY ASSURANCE

A. Regulatory Requirements: Comply with requirements of building authorities having jurisdiction in Project location.

B. Manufacturer Qualifications: Minimum five (5) years documented experience producing systems specified in this section.

C. Pre-Installation Meeting:

1. Convene at job site seven (7) calendar days prior to scheduled beginning of construction activities of this section to review requirements of this section.

2. Require attendance by representatives of the installing subcontractor, (who will represent the system manufacturer) and other entities directly affecting, or affected by, construction activities of this section.

3. Notify Architect four (4) calendar days in advance of scheduled meeting date.

1.07 DELIVERY, STORAGE AND HANDLING

A. Delivery: Deliver materials to site in manufacturer's original, unopened containers and packaging, with labels clearly indicating manufacturer and material.

B. Storage and Handling: Protect materials and finishes during handling and installation to prevent damage.

1.08 PROJECT CONDITIONS

A. Field Measurements: Take measurements of actual Roof top unit for fit without gaps. Indicate measurements on shop drawings fully documenting any field condition that may interfere with the screen system installation.

1.09 COORDINATION

A. Installer for work under this Section shall be responsible for coordination of panel and framing sizes and required options with the Contractor's requirements.

1. Request information on sizes and options required from the Contractor.

B. Submit shop drawings to the Contractor and obtain written approval of shop drawing from the Contractor prior to fabrication.

1.10 WARRANTY

A. If any part of the rooftop equipment screen fails because of a manufacturing defect within one year from the date of substantial completion, the manufacturer will furnish without charge the required replacement part(s). Any local transportation, related service labor or diagnostic call charges are not included.

B. This warranty does not cover failure of your rooftop equipment screen if it is damaged by the Owner, or if the failure is caused by improper installation. In no event shall Warrantor be liable for incidental or consequential damages.

PART 2 - PRODUCTS

2.01 MANUFACTURERS

A. Acceptable Products: "Envisor Screening System" by CityScapes Incorporated, 4200 Lyman Ct. Hilliard, OH 43026. 1-877-727-3367 www.cityscapesinc.com

B. Substitutions: Unistrut Component Materials.

2.02 MATERIALS

A. Thermoformed plastic Panels: Fabricated from rigid medium impact thermo-formed ABS (Acrylic Butylene Styrene) sheets.

1. Minimum thickness 3/16".

B. Framing: Aluminum Plate, Shapes and Bar: ASTM B 221, alloy 6061-T5 or 6063-T5.

C. Threaded Fasteners: All screws, bolts, nut and washers shall be Stainless steel.

1. Corner assembly fasteners shall be #10-16 x stainless steel TEK screws. Length as required to develop full holding capacity of screw when fastened to Mechanical Equipment.

2. Provide lock washer or other locking device at all bolted connections.

2.03 FABRICATION

A. Provide factory-formed panel systems with continuous interlocking panel connections and indicated or necessary components: Form all components true to shape, accurate in size, square and free from distortion or defects. Cut panels to precise lengths indicated on approved shop drawings.

1. Panel Style and Height: Vertical Style, 6' +/- (field verify) Louver, Step 2 Trim, custom color as selected by Architect. Coordinate panel installation w/ RTU mfg. & Tenant.
www.cityscapes.com.

B. Trim and Closures: Fabricated from 24 gage metal, and finished with the manufacturers standard coating system, unless shown otherwise on drawings.

1. Provide top trim as indicated:
- C. Framing: Fabricate and assemble components in largest practical sizes, for delivery to the site.
1. Construct corner assemblies to required shape with joints tightly fitted.
 2. Supply components required for anchorage of framing. Fabricate anchors and related components of material and finish as required, or as specifically noted.
- 2.04 FINISHES
- A. Aluminum Framing: Mill.
- B. Panel Coating: Manufacturer's standard coating system, factory-applied.
1. Color: Selected from full range of manufacturer's standard colors.
 2. Color: As selected by Owner/Architect

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Installer's Examination: Examine conditions under which construction activities of this section are to be performed.
1. Submit written notification to Architect and Screen manufacturer if such conditions are unacceptable.
 2. Beginning erection constitutes installer's acceptance of conditions.

3.02 INSTALLATION

- A. Install units in accordance with the manufacturer's instructions and approved shop drawings. Keep perimeter lines straight, plumb, and level. Provide brackets, anchors, and accessories necessary for a complete installation.
- B. Fasten structural supports to HVAC units without damaging operation of the unit.
1. Provide corner and mid-span assemblies as required by approved shop drawings so that the panels are supported uniformly.
 2. Fastening bottom rail using bolts to permit ease of access to HVAC units.
- C. Insert thermoplastic panels into structural supports, except where fixed attachment points are indicated. Butt thermoplastic panels to adjacent panels for uniform fit. Fasten fixed panels in accordance with the shop drawings.
- D. Metal Separation: Where aluminum materials would contact dissimilar materials, insert rubber grommets at attachment points, thus eliminating where dissimilar metals would otherwise be in contact.
- E. Do not cut or abrade finishes which cannot be restored. Return items with such finishes to shop for required alterations.

3.03 ERECTION TOLERANCES

- A. Maximum misalignment from true position: 1/4".

3.04 CLEANING AND PROTECTION

- A. Remove all protective masking from material immediately after installation.

- B. Protection:

- 1. Ensure that finishes and structure of installed systems are not damaged by subsequent construction activities.
- 2. If minor damage to finishes occurs, repair damage in accordance with manufacturer's recommendations; provide replacement components if repaired finishes are unacceptable to Architect.

- C. Prior to Substantial Completion: Remove dust or other foreign matter from component surfaces; clean finishes in accordance with manufacturer's instructions.

- 1. Clean units in accordance with the manufacturer's instructions.

END OF SECTION